

READYSPAN

Pre-Engineered FRP Pedestrian, Equestrian & Light Vehicle Bridge System

















APPLICATIONS

STATE PARKS | HIKING AND BIKING TRAILS | ATV AND EQUESTRIAN TRAILS | GOLF COURSES NEW BRIDGE INSTALLATIONS | REPLACEMENT BRIDGE INSTALLATIONS



Ready for Quick Shipping

Standard components are in stock and ready for immediate fabrication for quick shipping to wherever you need them. Plus, ReadySpan bridges can be delivered in three ways:

- A kit for complete assembly in the field
- In modules that require limited assembly
- Completely pre-assembled



Easy to Assemble

If you choose to assemble in the field, all components of ReadySpan bridges are shipped predrilled with the necessary hardware. The material is lightweight and requires no special experience or tools for assembly, so bridges can be assembled by virtually anyone.

CUSTOM-ENGINEERED SOLUTIONS AVAILABLE

Your bridge, your way. Our range of standard sizes expands your design possibilities. Many upgrades are available, too. So don't limit your thinking — just think ReadySpan and get it done.

STANDARD FEATURES

- FRP Channel Top Cap with Painted Finish for Additional
 UV Protection
- 2 3" x 12" Pressure-Treated Southern Yellow Pine Decking (ADA-Compliant HD Fiberglass Decking Available)
- 3 FRP Diagonal and Vertical Web Members
- 4 FRP Square Tubing Outrigger Supports
- 5 FRP Channel Crosspieces (x2)
- 6 Galvanized or Stainless Steel Foundation Anchor Clips

- 7 Straight or Sloped-End Designs
- 8 Standard 54" High Hand Railings (Higher When Required)
- 9 Safety Mid-Rails with ADA-Compliant Spacing
- A307 Hot-Dipped Galvanized Steel Hardware Kit (Stainless Steel Hardware Available)
- 11 Standard Colors: Olive Green or Brown
- 12 Upper and Lower Chord





ReadySpan Load Table

Based on the Aspect Ratio < 15

	P-SERIES Bridges (85 PSF Loading)				PV-SERIES Bridges (60 PSF / 85 PSF and H-5 Loading)			
SPAN/LENGTH	INTERIOR BRIDGE WIDTH							
	3'	4'	5'	6'	7'	8'	9'	10'
10'	•	•		•	•	•	•	•
15'	•	•	•	•	•	•	•	•
20'	•	•	•	•	•	•	•	•
25'	•	•	•	•	•	•	•	•
30'	•	•	•	•	•	•	•	•
35'	•	•	•	•	•	•	•	•
40'	•	•	0	•	•	•	•	•
45'	•	•	0	•	•	•	•	•
50'	•	•	•	•	•	•	•	•
55'		•	0	•	•	•	•	•
60'		•	0	•	•	•	•	•
65'			•	•	•	•	•	•
70'			•	•	•	•	•	•
75'			•	•	•	•	•	•
80'				•	•	•	•	•
85'				•	•	•	•	•
90'				•	•	•	•	•
95'					•	•	•	•
100'							•	•

QUICK-SHIP OPTIONS

Find a range of sizes in the ReadySpan P-Series for pedestrian bridges and PV-Series for pedestrian/light vehicle applications.

P-SERIES FOR PEDESTRIAN TRAFFIC

TYPICAL DIMENSIONS

DESIGN LOAD RATING Span/Length: 10' to 90' 85 PSF Uniform Live Load

Interior Bridge Width: 3' to 6'

PV-SERIES FOR PEDESTRIAN OR LIGHT VEHICLE TRAFFIC

TYPICAL DIMENSIONS

DESIGN LOAD RATING

Span/Length: 10' to 100' Interior Bridge Width: 7' to 10' 60/85 PSF Uniform Live Load 10,000 lbs. H-5 Vehicle Load

Structural calculations based on the size of bridge.

BEDFORD IN ACTION



MARTIN HILL ATV TRAIL PEDESTRIAN BRIDGES:

Buchanan State Forest, Bedford County, PA 30' span | Shipped loose for field assembly

For more real-world examples of our bridges, visit ReadySpan.com.



BANNER ELK PEDESTRIAN BRIDGE:

Banner Elk, NC

60' span | Truss sections shipped assembled; other components field-assembled



MADE IN THE U.S.A.

Bedford is a family-owned American company, and ReadySpan bridges are proudly built right here in Pennsylvania.



BEDFORD REINFORCED PLASTICS: ONE CORPORATE DRIVE, SUITE 106, BEDFORD, PA 15522 USA

The photographs and/or drawings in this literature are for illustrative purposes only. While every reasonable effort has been made to ensure the accuracy of this data, we are not responsible for any errors or omissions contained on these pages. Please verify any information in question with a Bedford sales representative. We reserve the right to make changes in specifications without notice and without incurring obligation.

© 2021 Bedford Reinforced Plastics. All rights reserved.